

# Sigma debuts in Dartford

Albion Sections' new Sigma purlins product has debuted on a warehouse project erected by Crown Structural in Dartford, Kent.

Sigma purlins are 10% more efficient than previous products and have less weight. For spans between 6m and 7m less accessories, such as sleeves and anti sag systems, are needed, which means less material cost and a quicker erection time.

John Jones, Managing Director, Albion Sections, said: "We are customer focused and

work extremely hard to provide customers with the tools needed to compete and offer improvements in their service.

"The main driver for the Sigma development was to combat rising costs, now that prices have fallen, our investment has not gone to waste as our customers have a competitive edge when choosing our purlins."

The 800m<sup>2</sup> distribution warehouse in Dartford, Kent required Crown to erect 50t of steelwork and 450m of Albion Sections' Sigma.

